

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/OW/WORK_INDENT11400

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/17/2013-14, Date: 09.01.2014

Maintenance of BBMP Drilled Borewells in ward no. 10, Doddabommasandra Vidyaranyapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				GOWDAPPA MURTHY	
				In Figures	In Words
1	30	Lifting of Submersible pump set as per Specification and direction (P. 56 / I. 10.3.21) PRED SR (2012-13)	Each	840.0	Rupees Eight Hundred Forty Only
2	30	Transportation of pumping machineries (P. 56 / I. 10.3.19) PRED SR (2012-13)	Each	890.0	Rupees Eight Hundred Ninety Only
3	30	Labour charges (over hauling) P. No. 56 / I No.10.3.22 PRED SR (2012-13)	Job	545.0	Rupees Five Hundred Forty Five Only
4	15	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. PRED SR (2012-13) P No. 54 / I. No. 10.1) (Above 10 HP upto 20 HP add Rs.150/- for every HP) A) 10 HP Motor upto 5 HP 2500.00 for 10 HP (120 x 10) 1200.00 Total 3700.00	No.	3650.0	Rupees Three Thousand Six Hundred Fifty Only
5	15	B) 12.5 HP Motor upto 5 HP 2500.00 for 12.5 HP (150 x 15) 2250.00 Total 4750.00	No.	4700.0	Rupees Four Thousand Seven Hundred Only
6	30	B) Replacement of Motor Parts: Starter (with one year Guarantee) P No. 55 / I No. 10.3.3 PRED SR (2012-13)	No.	5050.0	Rupees Five Thousand Fifty Only
7	30	Rotor (with one year Guarantee) P No. 55 / I No. 10.3.6) PRED SR (2012-13)	No.	4700.0	Rupees Four Thousand Seven Hundred Only
8	30	Upper Flange P. No. 56 / I No. 10.3.7 PRED SR (2012-13)	No.	340.0	Rupees Three Hundred Forty Only
9	30	Lower Housing P. No. 56 / I No. 10.3.10 PRED SR (2012-13)	No.	645.0	Rupees Six Hundred Forty Five Only
10	30	Carbon Housing P. No. 56 / I No.10.3.12 PRED SR (2012-13)	No.	470.0	Rupees Four Hundred Seventy Only
11	30	Thrust bearing block assembly complete with Segment bearing pad.P. No. 55 / I No.10.3.13 PRED SR (2012-13)	No.	1150.0	Rupees One Thousand One Hundred Fifty Only
12	30	C) Replacement of pump parts: The following main components of submersible pump sets requiring replacement. Oil Seal P. No. 54 / I No.10.2.3 PRED SR (2012-13)	No.	120.0	Rupees One Hundred Twenty Only
13	30	Oil Seal Steel Bush P. No. 54 / I No. 10.2.4 PRED SR (2012-13)	No.	150.0	Rupees One Hundred Fifty Only
14	450	Guide vane P. No. 54 / I No. 10.2.5 PRED SR (2012-13)	No.	175.0	Rupees One Hundred Seventy Five Only
15	450	Impeller Shell moulded with aluminium Bronze) P. No. 54 / I No. 10.2.6 PRED SR (2012-13)	No.	425.0	Rupees Four Hundred Twenty Five Only
16	30	Discharge outlet (D.O) Bearing D.O Steel Bush P. No. 55 / I No. 10.2.7 PRED SR (2012-13)	No.	440.0	Rupees Four Hundred Forty Only
17	30	Steel Bush P. No.55 / I No. 10.2.9 PRED SR (2012-13)	No.	150.0	Rupees One Hundred Fifty Only


Executive Engineer
 Byatarayanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

18	30	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) P. No. 55 / I No. 10.2.11 PRED SR (2012-13)	No.	940.0	Rupees Nine Hundred Forty Only
19	30	Non – return valve (NRV) assembly complete with rubber 'O' Ring P. No. 55 / I No. 10.2.14 PRED SR (2012-13)	No.	1350.0	Rupees One Thousand Three Hundred Fifty Only
20	30	Cable Guard P. No. 55 / I No. 10.2.15 PRED SR (2012-13)	No.	145.0	Rupees One Hundred Forty Five Only
21	30	Brass Filter P. No. 55 / I No. 10.2.17 PRED SR (2012-13)	No.	250.0	Rupees Two Hundred Fifty Only
22	30	Re-erection charges of pumping machineries including overhauling and pointing P. No. 56 / I No. 10.3.20 PRED SR (2012-13)	Each	945.0	Rupees Nine Hundred Forty Five Only
23	37.13	D) General Items Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following structure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil	cum	184.0	Rupees One Hundred Eighty Four Only
24	110	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and includng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13.	rmtr	156.0	Rupees One Hundred Fifty Six Only
25	37	Refilling the basement and pipeline treanches with seclated available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13	cum	60.0	Rupees Sixty Only

Mustaf

Signature of the Contractor

D. E. Open

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92